

**GENERAL AND TECHNICAL FEATURES OF
“EPIC FOR NAZILLI-İZMİR NATURAL GAS TRANSMISSION PIPELINE PROJECT, PHASE-3”**

Sl. No.	Name of the Contract Executed	Client	Value of Contract	Completion Date	Description of Works Undertaken
04	EPIC for Nazilli-İzmir Natural Gas Transmission (cross-country) Pipeline Project, Phase-3 Nazilli-İzmir /TURKEY	BOTAŞ Petroleum Pipeline Corp.	US\$16.582.135	09.03.2007	<p>57.624 m. 40” API5L Gr.X65 high pressure (O.P.75 bar) natural gas transmission pipeline construction with all related pipeline facilities and activities complying with API, ASME and ANSI standards.</p> <p>Assembly and Installation of 2 ea. 40” Class 600 Line Valve Groups, 1 ea. 10” Class 600 Take-Off Valve Groups with concerning mechanical, civil and electrical works.</p> <p>Assembly and Installation of 1 ea. 10”x14” Pig Station.</p> <p>All hydrostatic testing, pre-commissioning and commissioning activities.</p>

All line pipes and valve materials in the scope of the Project has been procured and free issued by the CLIENT (BOTAŞ) and delivered to İNDET for Project execution.